

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-30071-00-00  
Spot: NWNE Sec/Twnshp/Rge: 20-23S-19W  
4648 feet from S Section Line, 1958 feet from E Section Line  
Lease Name: PLOGER Well #: 1  
County: EDWARDS Total Vertical Depth: 4900 feet

Operator License No.: 31074 •  
Op Name: BRAKE, JOE DBA BRAKE INC.  
Address: RT 1 BOX 84  
LATHAM, KS 67072

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4115		WITH 2 SX CMT
SURF	8.625	283		WITH 185 SX CMT
PROD	5.5	4600	1820	WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/17/2012 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SET CIBP @ 4400' & 2 SX CMT. SET CIBP @ 4140' & 2 SX CMT. PLUG AT 1360' WITH 20 SX GEL & 50 SX CMT. PLUG AT 560' WITH 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/17/2012 3:46 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

COULDN'T GET BRIDGE PLUG PAST 4120'. SET CIBP @ 4115' WITH 2 SX CMT ON TOP WITH DUMP BAILER. RAN TBG TO PLUG THROUGH DUE TO MULTIPLE HOLE IN CASING. 1ST PLUG AT 1364' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 558' WITH 50 SX CMT. 3RD PLUG AT 309' WITH 50 SX CMT. 4TH PLUG AT 42' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4499	4505		MISSISSIPPI
4190	4192		LANSING

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

RECEIVED  
JAN 25 2012  
KCC WICHITA

District: 01

Signed Richard M. Lacey  
(TECHNICIAN)

RECEIVED  
JAN 20 2012  
KCC DODGE CITY

[Signature]  
Form CP-2/3  
1/30/12