

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23983-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 34-16S-24W
330 feet from S Section Line, 1320 feet from E Section Line
Lease Name: HORCHEM Well #: 2
County: NESS Total Vertical Depth: 4875 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4370		WITH 2 SX CM T
SURF	8.625	225		WITH 140 SX CMT
PC		1814		WITH 120 SX CMT
PROD	5.5	4570	0	WITH 305 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/17/2012 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: JOE SMITH Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 01/17/2012 2:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

SET CIBP @ 4370' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. RUN TBG IN TO 1830'. CIRCULATE CMT TO SURFACE INSIDE 5 1/2" CASING WITH 170 SX CMT. LAID TBG DOWN & TOP OFF 5 1/2" CASING WITH 5 SX CMT. TIED ONTO 5 1/2" X 8 5/8" ANNULUS. PUMPED DOWN ANNULUS WITH 25 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4494	4497		
4422	4426		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

RECEIVED
JAN 25 2012
KCC WICHITA

District: 01

Signed

Steve Durrant

(TECHNICIAN)

RECEIVED
JAN 24 2012
KCC DODGE CITY