

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-20114-00-00
Spot: CN2SWNW Sec/Twnshp/Rge: 22-15S-3W
3630 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: WEISGERBER Well Number: 1
County: SALINE Total Vertical Depth: 3415 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 3415 300 SX
Surface Casing Size: 8.625 feet: 354 225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/12/2003 1:00 PM

Plug Co. License No.: 101 Plug Co. Name: KCC FEE FUND

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Per KCC instructions.

RECEIVED
KCC DISTRICT #2
MAR 25 2003
03-25-2003
WICHITA, KS

Plugging Proposal Received By: RALPH TITTEL

Witness Type: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 02/17/2003 10:00 AM

KCC Agent: RALPH TITTEL

Actual Plugging Report:

Ran tubing to 3150 spot 35 sx. Pull tubing, shot 5 1/2" @ 450'. Ran tubing to 450' - circulated cement to surface. 2/17/03 - 1 1/2 yds. Slurry mix to top off well. Smokey Valley Redi Mix 1 1/2 yds.

Remarks: UNITED CEMENTING #4497 - 168 SX 60/40 POZ 4% GEL CONTROL #2003-0041-001

Plugged through: TBG

District: 02

Signed Ralph Tittel
(TECHNICIAN)

15-169-20114-00-00

W E L L L O G

Well Name: #1 Weisgerber Operator: Wheatland Oil & Gas, Inc.
 Spud Date: 10-21-80 Contractor: Ramco Drilling Corp.
 Completion Date: 10-29-80 Casing: 8-5/8" @ 354' w/ 225 sx.
 Location: C N/2 SW NW Sec. 22-15S-3W Common, 3% CaCl., 2% Gel.
 Saline County, Kansas 4 1/2" @ 3415 w/ 300 sx.

FORMATION	FROM	TO
Sand & Shale	0	298
Fort Riley	298	354
Sand & Shale	717	1090
Sand & Shale	1090	1852
Shale	1852	2157
Shale & Lime	2157	2545
Lime & Shale	2545	2662
Shale	2662	2970
Lime & Shale	2970	3061
Shale	3061	3205
Shale & Lime	3205	3315
Lime	3315	3415
Rotary Total Depth		3415

RECEIVED
STATE CORPORATION COMMISSION

APR 13 1982

CONSERVATION DIVISION
Wichita Kansas

04-13-1982

STATE OF KANSAS, COUNTY OF BUTLER: ss


I certify that the above information is true and correct to the best of my knowledge.

THE RAMCO DRILLING CORPORATION

J. V. Crawford, Vice President

Subscribed and sworn to before me on this 5th day of November, 1980

Sandra Kay May
Sandra Kay May Notary Public



My appt. exp: