

5 040376

2-18-88

135

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1-18-62 15-169-00432-00-8

NW SW NE , SEC. 29 , T 14 1 S, R 2 WXX
3630 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6737
Operator: L. B. Jackson Co.
Name & Address 4609 E. 31st Street
Tulsa, OK 74135

Lease Name Oliver Well # 1
County Saline 109.20
Well Total Depth 3360 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor L. B. Jackson & Howco License Number
Address

Company to plug at: Hour: 8:00am Day: 18 Month: 2 Year: 19 88

Plugging proposal received from John Helm
(company name) L.B. Jackson (phone)

were: Pump 1 hulls, 35 sxs cement through tubing to TD to seal off perfs @3277-87,
TD @3360 4 1/2" @3360 w/100 sxs. Gel to 1400' where packersis stuck. Shoot
off 50' above packer. Circulate cement to surface through tubing. Pull tubing.
Pump 75 sxs cement into 8 5/8" & 4 1/2" annulus

Plugging Proposal Received by Ralph Tittel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:00pm Day: 18 Month: 2 Year: 1988

ACTUAL PLUGGING REPORT Tried to circulate through 2"--Plugged @250'--Unscrewed 2" from packer
and pull 1800' of 2". Pumped down 4 1/2"--open to TD. Pumped 35 sxs cement, 1 hulls,
26 bbls bud, 100 sxs cement. Close in @200# on 4 1/2". Pumped 7 bbls mud, 1 sxs hulls,
75 sxs cement down 8 5/8" and 4 1/2" annulus. Shut in @500#.

Will dig out and cut off @4"--Clean up location

Remarks: Howco #361217
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-29-88

INV. NO. 19928 W

2-18 MAR 24 1988

FEB 23 1988

CONSERVATION DIVISION
Wichita

Signed Ralph Tittel
(TECHNICIAN)

FORM CP-2/3
Rev. 01-84