

5 040388

5-16-88 15-169-00414-00-00 360
API NUMBER 15- 5-14-64
C SW NE, SEC. 17, T 14 S, R 2 W/EX

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6819

Operator: Scott's Well Service

Name & Address: Box 36

Roxbury, KS 67476

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Scott's Well Service License Number 6819

Address Roxbury, KS

Company to plug at: Hour: 4:00pm Day: 16 Month: 5 Year: 19 88

Plugging proposal received from Jay Scott

(company name) Scott's Well Service (phone) _____

were: Try to get to bottom and sand to 3150', cap with 4 sxs. Recover 4 1/2".

Bail to 350' and redimix to surface.

Plugging Proposal Received by Ralph Tittel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30pm Day: 16 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT Tried to run bailer, Bridge @40', pipe parted @40', Pulled 4 1/2"

1 joint had 4 1/2" X 5 1/2" swedge on end. Was setting on 4 1/2" (This was abd. producer made into unpermitted SWD, no tubing used) Ran bailer and got into 4 1/2". Started to bail down hole, fluid @base of surface pipe. Pulled old piece of 4 1/2" out of hole w/bailer. Bailed to 550', hit another solid bridge, check hole w/mirror and found 4 1/2" in center of 8 5/8", this allows cement inside and out. Ordered 5 yards redimix and filled hole to surface.

Remarks: Salina Concrete Products truck #58
Additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 6-22-88 DIVISION CONSERVATION DIVISION Kansas
INV. NO. 207

WK

Signed Ralph Tittel (TECHNICIAN)