

5 040392

5-20-88 15-169-00413-00-00 359 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 12-3-63
C NE SE, SEC. 17, T 14 S, R 2 W XX

TECHNICIAN'S PLUGGING REPORT

1980 feet from S section line
660 feet from E section line

Operator License # 6819

Lease Name ~~Vanner~~ Vanier Well # 1

Operator: Scott's Well Service

County Saline 103.97

Name & Address Box 36

Well Total Depth 3199 feet

Roxbury, KS 67476

Conductor Pipe: Size _____ feet

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Scott's Well Service License Number 6819

Address Roxbury, KS

Company to plug at: Hour: 2:00pm Day: 19 Month: 5 Year: 19 88

Plugging proposal received from Jay Scott

(company name) Scott's Well Service (phone) _____

were: Sand to 3150' and cap with 4 sxs cement. Recover 4 1/2". Bail to 400.

Set solid bridge and redimix to surface.

Plugging Proposal Received by Ralph Tittel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30am Day: 20 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT Ran bailer to check TD. Sand back to 2750' and cap with 4

sxs cement. Recovered 400' of 4 1/2". Hole caved in to 200' after pulling 4 1/2".

No fluid, so redimixed to surface with 4 yards redimix.

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS

MAY 25 1988

Remarks: Salina Concrete
(If additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

W Signed Ralph Tittel
(TECHNICIAN)

DATE 6-22-88

INV. NO. 20942