

2-090387

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

15-169-00453-00-00

10-27

API NUMBER: E-23,272

W/2,NW,NW, SECTION 08 TOWNSHIP 15 RANGE 02W

OPERATOR LICENSE # 6306

4620 FEET FROM S SECTION LINE

4950 FEET FROM E SECTION LINE

OPERATOR TOM BROWN CONT.

NAME & 4608 N. CRYSTAL SPRINGS, RD

ADDRESS SALINA, KS 67401

LEASE NAME: WAUHAB #1

COUNTY: SA Saline

WELL TOTAL DEPTH: 3428' 111.41

PIPE: _____

SURFACE CASING: 8 5/8" @ 273'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL X SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SCOTTS WELL SERVICE

ADDRESS: _____ LICENSE: 6819

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 18 MONTH: 10 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: JOY SCOTT

COMPANY NAME: SCOTTS WELL SERVICE PHONE: 913-254-7828

WERE: SAND TO 3150' C/W 5 XS. CMT. SHOOT CASING @ 350'.
SLURRY TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY: R.TILLEL

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART (_____) NONE (_____)

COMPLETED: HOUR: 12:00 DAY: 27 MONTH: 10 YEAR: 1995

ACTUAL PLUGGING REPORT:

PULLED 2 3/8" TUBING PARTED @ 1200' WASHED OVER &
RECOVERED 800' MORE TO 2000'. TRIED TO WASH OVER & DRL.
OUT SOLID BRIDGE @ 2000'. RAN 2" TO 1950' SPOT 50 XS.
CMT. LET SET OVERNITE TOP CMT. 1450' NEED MORE CMT. RAN
2" SPOT 100 XS. @ 1450'. TIED TO 5 1/2" & SQUEEZED TO
300' SHUT IN OVERNITE.

REMARKS: UNSCREW 5 1/2" @ 360' SB. 6 YDS. SLURRY TO SURFACE. SALINE CMT.

I DID OBSERVE THIS PLUGGING.

Ralph Tittel
Ralph Tittel (AGENT)

FORM CP-2/3
REV. 3/90

INVOICED

DATE 11-3-95

INV. NO. 43932

10-27

FEB 06 1996

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 01 1995

CONSERVATION DIVISION
WICHITA, KS