

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-169-19072-00-00

SE/4, Sec. 6, T 15 S, R 2 W/8

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5415

Lease Name Swigert Well # 2

Operator: MULTI STATES OIL PROPERTIES

County Saline 105.11

Name & Address 3000 United Founders Blvd.  
OKLAHOMA CITY, OK 73112

Well Total Depth 3234 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 235

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated 5 1/2" @ 3229

Plugging Contractor Kelso Casing Pulling License Number 6050

Address CHASE, KANSAS

Company to plug at: Hour: 2 PM Day: 8 Month: OCTOBER Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Edd HARRISON

(company name) MULTI STATES OIL PROPERTIES (phone) \_\_\_\_\_

were: They wish to set Cement retainer @ 3183' plug off by squeezing 75 sac 6 3/4 Poz 2 gel through tubing, and placing 5 sac above retainer. Max Psi - 900. Cement above Retainer @ 3111'.

Casing shot off @ 2300' and recovered. Pumped 3 sac hulla, 20 gel, 125 sac 5/50 Poz 3 gel down 8 7/8 Casing.

Signed Merlan W. Murrah  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:00 PM Day: 15 Month: Nov Year: 19 84

ACTUAL PLUGGING REPORT Cement retainer set @ 3183' Squeezed through

tubing 75 sac Cement w/ 5 sac (approx) above retainer. Found Cement above retainer w/ measuring line to be @ 3111'. Shot off Casing @ 2300' & pulled out of hole. Pumped 3 sac hulla, 20 sac gel, released plug, followed w/ 125 sac 5/50 Poz mix 3 gel through

flowed plug Container on 8 7/8 Casing. Max Psi 700 Shut in @ 400'

Remarks: Rec. 2300' of 5 1/2"

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 26 1984  
CONSERVATION DIVISION  
Wichita, Kansas

Halliburton ticket # 890615-B-420898 on 10/9/84

Halliburton ticket # 890761-B-459294 on 11/15/84

I hereby certify that the above plugging instructions were given as herein stated and that I  (did)  (did not) observe this plugging.

Signed Merlan W. Murrah  
(TECHNICIAN)

INVOICED

DATE 12-4-84

INV. NO. 5760