


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

SALINE

County. Sec. 7 Twp. 14 Rge. 2 (E) 2 (W)

Location as "NE/CNW/SW" or footage from lines SE NE SW
Lease Owner CHARLES E. PETREY
Lease Name PUTMAN PUTMAN NO. 4 Well No. _____
Office Address 1300 N MAPLE MC PHERSON KANS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed 6-28-1947 19____
Application for plugging filed AUG. 24 - 1955 19____
Application for plugging approved 11 11 11 19____
Plugging commenced SEPT 20-55 19____
Plugging completed SEPT 24-55 19____
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production SEPT 15 1955

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well RUEL BURKEE
Producing formation VIOLA Depth to top 3186 Bottom 3188 Total Depth of Well 3190 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>VIOLA</u>	<u>OIL</u>	<u>3186</u>	<u>3188</u>	<u>5 1/2"</u>	<u>3186</u>	<u>2702</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

DUMPED 6 SACKS OF CEMENT AT 3175 FT. SHOT BUPE OFF AT 2702 FT. PULLED PIPE AND MUDDING HOLE TO 175 FT. SET ROCK BRIDGE AND DUMPED 25 SACKS OF CEMENT AT 175 FINISHED MUDDING HOLE TO 135 FT. SET ANOTHER ROCK BRIDGE AND DUMPED 15 SACKS OF CEMENT AT 135 FT. FINISHED MUDDING HOLE AND DUMPED 5 SACKS OF CEMENT AT BASE OF CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

OCT 1 1955

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor BERTSELF
Address R.R. HUTCHINSON Kans.

STATE OF KANS. COUNTY OF RENO ss.

EMPLOYEE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

R. R. 4 HUTCHINSON-KANS.

(Address)

28TH

day of

SEPT

19

55



AUG. 12 - 57

Notary Public.

PLUGGING
FILE SEC 7 T 14 R 20
BOOK PAGE 145 LINE 29

15-129 - 00702-0000

SE NE SW Sec 7-14S-2W
 Saline County, Kansas
 Elevation 1217'
 Well drilled June 1947

Ssg. record
 152' of 8 5/8" Cemented with 130 sacks
 3198' of 5 1/2" " " " "

3186

Soil	0	15
Sand & Shale	15	65
Shale & Shells	65	106
Lime & Shale	106	138
Shale & Sand	138	148
Shale & Shells	148	152
Shale & Shells	152	175
Anhydrite	175	230
Shells & Shells	230	255
Lime & Shale	255	1505
Lime	1505	2875 1575
Lime & Shale	1575	1685
Shale	1685	1710
Lime	1710	1790
Shale & Lime	1790	2030
Lime	2030	2065
Lime & Shale	2065	2505
Shale	2505	2666
Lime	2666	2684
Chat & Lime	2684	2700
Lime	2700	2805
Shale	2805	2932
Shale	2932	3010
Lime	3010	3108
Shale	3108	3189
Viola	3189	3190

Cable Tool Log

3165	3189	Float Cement & Shoe
3189	3190	Cement (Show of Oil
3190	3190 1/2	oil increase

PLUGGING
 FILE SEC 7 14 S 2 W
 BOOK PAGE 145 LINE 29

Duck