


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

15-169-00175-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Saline County. Sec. 5 Twp. 14S Rge. 2 (W)  
Location as "NE/CNW/SW" or footage from lines SW SE SW  
Lease Owner De Weese & Sanderson  
Lease Name Winslow Well No. 1  
Office Address Salina - Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 22 19 53  
Application for plugging filed November 22 19 53  
Application for plugging approved November 22 19 53  
Plugging commenced November 22 19 53  
Plugging completed November 23 19 53  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation Depth to top Bottom Total Depth of Well 3200 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Maquoketa Dolomite	S S O	3185	3200	8 5/8"	292	Cmtd w/ 250 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Loaded with heavy mud  
Set bridging plug at 185'  
15 sacks cement through drill pipe at 180'  
Heavy mud to 30'  
5 sacks cement to surface

RECEIVED  
STATE CORPORATION COMMISSION  
DECEMBER 12-03-53  
CONSERVATION DIVISION  
WICHITA

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Shields Drilling Company, Inc.  
Address Box 248 - Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
H. E. Reiss (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. E. Reiss*  
Box 248 - Russell, Kansas  
(Address)



SUBSCRIBED AND SWORN to before me this 2nd day of December, 19 53.

May 28 - 1955

24-7368-5 3-53-20M

PLUGGING  
FILE SEC 5 T 14 R 2W  
BOOK PAGE 145 LINE 7

Notary Public.

WELL LOG

15-169-00175-00-00

De Weese & Sanderson  
WINSLOW #1

SW SE SW  
Sec 5, Twp 14S, Rge 2W  
Saline County, Kansas

Total Depth: 3200'  
Commenced: November 11, 1953  
Completed: November 22, 1953  
Drilled by Shields Drig. Co., Inc.

*Eslebeck*

CASING RECORD

8 5/8" @ 292' Cmtd. w/ 250 sax

Elevation: 1213' RB  
Production: D & A

MADE IN U.S.A.

----- Figures Indicate Bottom of Formations -----

Sand	100
Shale	130
Lime	175
Lime	260
Shale, shells & Red Bed	275
Lime	300
Lime & Shale	335
Shale, shells & Red Bed	415
Lime	535
Lime & Shale	670
Shale & Red Bed	690
Shale	1235
Salt & Shale	1270
Shale & Shells	1405
Lime & Shale	2400
Shale	2435
Lime & Shale	2500
Shale	2702
Lime & Shale	2867
Shale & Lime Streak	2938
Lime & Shale	3200 T D

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 27 1953  
REGISTRATION DIVISION  
TOPEKA, KANSAS

*Eslebeck*

PLUGGING  
FILE SEC 5 T 14 R 2W  
BOOK PAGE 45 LINE 7

*City Onion Skin*

MADE IN U.S.A.