

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

WELL PLUGGING RECORD

Saline County. Sec. 5 Twp. 14 Rge. 2 (E) (W)
 Location as "NE/CNW/SW" or footage from lines C SW NW
 Lease Owner Donald T. Ingling
 Lease Name Wessling Well No. 1
 Office Address 615 First National Bldg., Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) dry hole
 Date well completed 2-23 1963
 Application for plugging filed 3-27 1963
 Application for plugging approved 3-31 1963
 Plugging commenced 4-01 1963
 Plugging completed 4-04 1963
 Reason for abandonment of well or producing formation dry hole

NORTH

X			

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3203 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	207	none
				4 1/2	3174 1/2	1717.98

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand from 3203 to 3180 feet and dumped 4 sacks cement.
 Set ~~XX~~ rock bridge from 200 to 190 feet and dumped 20 sacks cement.
 Mud hole to 40 feet, set 10 foot rock bridge from 40 to 30 feet
 dumped 10 sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION

APR 23 1963

CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Kent Well Servicing Company
 Address Box 470, El Dorado, Kansas


STATE OF Kansas, COUNTY OF Butler, ss.
 _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mary Payne

 (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of April

My commission expires June 18, 1963



Donald T. Ingling et al, Lease Owner

Section 5-14-2W

Donald T. Ingling, Contractor

Location: 0 SW NW

Commenced: 2-13-63

County: Saline

Completed: 2-23-63

Production:

Total Depth: 3178' (rotary)

Elevation:

Casing: 8 5/8" 207' (100 sacks cement)
4 1/2" 3174 1/2' (50 sacks cement)

Figures below indicate bottom formation

- 40 surface clay
- 80 sand
- 120 shale and sand
- 190 lime
- 207 shale
- 320 lime and shale
- 550 shale and lime streaks
- 695 lime and shale streaks
- 880 shale and lime streaks
- 1220 shale and shells
- 1480 shale and shells
- 1625 lime and shale
- 1790 lime and shale
- 1940 shale and lime streaks
- 2035 lime
- 2190 lime and shale
- 2320 lime
- 2440 shale and lime streaks
- 2605 shale and lime streaks
- 2697 shale and lime streaks
- 2800 lime
- 2854 shale and lime streaks
- 2905 shale
- 2976 shale - Hunton Top
- 3035 lime - Hunton
- 3095 lime
- 3160 shale
- 3174 shale - Maquoketa
- 3178 dolomite - Maquoketa
- 3178 Total Depth

RECEIVED
STATE CORPORATION COMMISSION

MAR 28 1963

CONSERVATION DIVISION
Wichita, Kansas

3203 Cable tool T. D.

I certify this is a true and correct copy of the above mentioned well.

STATE OF KANSAS)
SEDGWICK COUNTY) ss.

Donald T. Ingling

Subscribed and sworn to before me a Notary Public in said county and state.

ME Black

My commission expires: Feb. 27, 1964

