

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Saline

County. Sec. 23 Twp. 15 Rge. 2 (E) 2 (W)Location as "NE/CNW/SW" or footage from lines CSE NELease Owner Dale ReeseLease Name MajorWell No. 1Office Address 913 United Bldg. Salina, KansasCharacter of Well (completed as Oil, Gas or Dry Hole) dry holeDate well completed 3/24 19 67Application for plugging filed " 19 67Application for plugging approved " 19 67Plugging commenced " 19 67Plugging completed " 19 67Reason for abandonment of well or producing formation dry holeIf a producing well is abandoned, date of last production 19Was permission obtained from the Conservation Division or its agents before plugging was commenced? yesName of Conservation Agent who supervised plugging of this well TomanProducing formation Depth to top Bottom Total Depth of Well 2728 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	117	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud from 2728' to 110', set plug at 110', put 20sx cement on plug, filled hole to 40' with mud, set plug at 40', put 10sx cement on plug. 2sx cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION

APR 11 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Melland Drilling co., Inc.Address Box 783, McPherson, KansasSTATE OF Kansas, COUNTY OF McPherson, ss.Donald J. Melland(employee of owner) or (~~owner~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 783, McPherson, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 19 67My commission expires May 7, 1968

Notary Public.

WELL RECORD

LEASE: Major

WELL NO. 1

ELEVATION: 1288RB

LOCATION: CSE NE
Sec. 23-15-2W

COMMENCED: 3/18/67

COMPLETED: 3/24/67

OPERATOR: Melland Drilling Co., Inc.

CONTRACTOR: Melland Drilling Company, Inc.
Post Office Box 783
McPherson, Kansas

CASING RECORD: 8 5/8" @ 117'/85sx

FORMATION	LOG
clay, shale & shells	117
shale & lime	309
lime & shale	750
shale	878
shale & shells	1245
shale	1517
lime & shale	1562
shale & lime	1790
lime & shale	1953
shale & lime	2153
lime & shale	2720
Mississippi	2728
RTD	2728

Sample Tops

Lansing	2079
Mississippian	2704

RECEIVED
STATE CORPORATION COMMISSION

APR 11 1967

CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATE

State of Kansas, County of McPherson, ss.

I, Donald J. Melland, do hereby certify that the above is a true and correct copy of the log of the above named and described well, as reflected by the records of the Melland Drilling Company, Inc.

Donald J. Melland

Subscribed and sworn to before me, a Notary Public, in and for the County of McPherson, State of Kansas,

this 6th day of April, 1967

My Commission expires: May 7, 1968

Notary Public