

15-169-00215-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Saline County, Sec. 18 Twp. 15 Rge. (E) 2 (W)

Location as "NE/CNW/SW" or footage from lines NW SE NW
Lease Owner E. H. Riggs
Lease Name Jilka Well No. 1
Office Address 1107 Union National Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed July 26 19 63
Application for plugging approved 19
Plugging commenced August 3 19 63
Plugging completed August 6 19 63
Reason for abandonment of well or producing formation depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 6-1 19 63
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3243 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	281	8 5/8"	281	none
		0	3239	5 1/2"	3239	2623.43

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 3225', set 10' rock bridge and dumped
5 sacks of cement.

Bail hole down to 280'. Build bridge with rock to 260'.
Dump 3 yards of redi-mix concrete to surface.

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Dean Wells (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Wells
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of August, 19 63

My commission expires ~~July 10, 1964~~ Feb. 10, 1967

George A. Meyer
Notary Public.



KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-169-00215-00-00

COMPANY **E. H. Riggs**

SEC. **18** T. **15** R. **2W**

FARM **Jilka**

NO. **1**

LOC. **NW SE NW**

TOTAL DEPTH **3243'**

COUNTY **Saline**


COMM. **10-19-61**

COMP. **10-27-61**

KANSAS

SHOT OR TREATED

CONTRACTOR **SeRoBee Drilling Co., Inc.**



ISSUED

CASING

20 10
 15 8-5/8" 281' W/250 sax
 12 6
 13 5-1/2" 3239' W/75 sax

ELEVATION **1253 DF**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0	-	20	Surface shale
20	-	60	Sand
60	-	155	Shells & shale
155	-	260	Lime
260	-	270	Shale & lime
270	-	281	Lime
281	-	350	Sandy shale
350	-	485	Lime with shale streaks
485	-	845	Lime & shale
845	-	855	Sand
855	-	1090	Shale & lime streaks
1090	-	1590	Shale & lime shells
1590	-	2360	Shale & lime
2360	-	2525	Sandy shale & lime
2525	-	2615	Lime & shale
2615	-	2655	Sandy shale
2655	-	2763	Shale & lime
2763	-	2787	Lime & chat
2787	-	2938	Lime & chert
2938	-	2960	Lime
2960	-	3140	Shale
3140	-	3155	Lime
3155	-	3173	Shale
3173	-	3243	Shale & lime
		3243	TD

RECEIVED
 STATE CORPORATION COMMISSION

JUL 29 1963

CONSERVATION DIVISION
 Wichita, Kansas