

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-169-00805-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Saline

County. Sec. 14 Twp. 15S Rge. (E) 2 (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW

Lease Owner Loren W. Hallam

Lease Name Forsberg Well No. 1

Office Address Salina, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 19

Application for plugging filed 19

Application for plugging approved 6-17-52 19

Plugging commenced 6-16-52 19

Plugging completed 6-16-52 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production Dry Hole 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Ruel Durkee

Name of Conservation Agent who supervised plugging of this well
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2814 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand to 2790'
6 sacks cement at 2790'
Mud to 170'
Rock, 170' to 160'
25 sacks cement at 160'
Mud to top
5 sacks cement at base of cellar.

STATE CORPORATION COMMISSION
SEP 20 1952
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Loren W. Hallam
Address Salina, Kansas

STATE OF Kansas, COUNTY OF Saline, ss.
Loren W. Hallam (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Loren W. Hallam

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of September, 1952

My Commission Expires May 17, 1953

Notary Public



24-2675-S 2-52-20M

PLUGGING
FILE SEC 14 T 15 R 22
BOOK PAGE 22 LINE 42

Loren W. Hallam, et al - Operator
 Box 566
 416 W. Jewell Street
 Salina, Kansas

Elevation: 1360 K. B.
 10-3/4" x 7" Head 6.85'
 below K. B.

Foursberg #1
 SE SE NW
 Sec. 14-15S-2W
 Saline County, Kansas

Casing Record:
 10-3/4" Csg. 130' w/75 sz
 7" OD Csg. 2800' w/50 sz

Well Commenced: 1- 6-52
 Well Completed: 1-16-52

Contractor: E. K. Carey, Contractor (Rig #2) Box 620, McPherson, Kansas
 Geologist: Don H. Smith, 5206 E. Central, Wichita 6, Kansas

Figures Indicate Bottom of Formation K.B.

Cellar	7
Shale	65
Shale & shells	230
Lime	247
Shale & lime	410
Lime & shale	730
Lime	810
Shale & shells	1125
Shale & lime	1320
Shale & shells	1680
Lime	1750
Lime & shale	1970
Shale & shells	2000
Sandy lime	2050
Shale	2138
Lime	2290
Lime & shale	2360
Lime	2475
Lime & shale	2575
Shale & lime	2794
Lime	2810 TD

Geologist Tops:
 Lansing K. C. 2170 (-810)
 Approx. Base K.C. 2496
 " Cherokee shale 2689 corr.
 Burgess sand 2793 (-1433) no show
 Mississippi 2794 (-1434)
 Pay - 2802 - 10
 Total Depth 2810 (-1450)
 Set 7" casing @ 2800' or 10' off
 bottom

The above Rotary Driller's Log is complete and correct to the best of my knowledge.

RECEIVED
 STATE DEPARTMENT OF GEOLOGY
 DIVISION OF OIL AND GAS
 E. K. CAREY, CONTRACTOR

CONSERVATION DIVISION
 By Herbert Rhoton
 Herbert Rhoton, Supt.

PLUGGING
 FILE SEC 14 T 15 R 22
 BOOK PAGE 22 LINE 42


15-169-00805-00-00

This is to certify that the information given is to the best of my knowledge true and correct.

E. K. CAREY, CONTRACTOR

By Herbert Rhoton
Herbert Rhoton, Superintendent

Subscribed and Sworn to before me this 23rd day of September 1952



E. K. Carey
Notary Public

My Commission Expires 11-13-52