


15-189-20050-00-00
Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Saline County, Sec. 14 Twp. 15 Rge. 2 (EX) (W)

Location as "NE/CNWxSWx" or footage from lines SE SW NW

Lease Owner George R. Hess & Larry Moore Ranch, Inc.

Lease Name MELANDER Well No. 1

Office Address 505 N. Charles, McPherson, Kansas 67460

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 2, 1971

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 19

Plugging completed May 2, 1971

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale & Lime		0	129	8 5/8"	129"	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

THIS WELL IS CLEAN OF IRON

Filled with mud to 125 ft., set plug and put in 25 sacks of cement. Filled with mud to 40 ft. and set plug. Put in 10 sacks of cement, 2 sacks in rathole. Plugging completed at 7:00 P. M., May 2, 1971. Plugging completed by State Plugger, Gilbert Toman.

Clean hole. Nothing left in this hole ^{But mud} left.


RECEIVED
STATE CORPORATION COMMISSION
MAY 5 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor BLACKSTONE DRILLING, INC.
Address Box 455, McPherson, Kansas 67460

STATE OF Kansas, COUNTY OF McPherson, ss.
George R. Hess & Larry Moore Ranch, Inc. (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) by: *George R. Hess*
505 N. Charles, McPherson, Kansas 67460
(Address)

SUBSCRIBED AND SWORN to before me this 4 day of May, 1971



Carroll D. Winslow

Notary Public.



15-169-20050-00-00

Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS 67460

May 3, 1971

COMPANY: GEORGE R. HESS & LARRY MOORE RANCH, INC.
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: MELANDER # 3
 LOCATION: SE SW NW, Sec. 14-15-2W
 Saline County, Kansas
 COMMENCED: April 27, 1971
 COMPLETED: May 2, 1971
 ELEVATION: 1365 K. B.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 5 1971
 CONSERVATION DIVISION
 Wichita, Kansas

0	to	790	Shale & Lime
790	to	1065	Lime & Shale
1065	to	1790	Shale & Lime
1790	to	2585	Lime
2585	to	2617	Lime & Shale
2617	to	2824	Burgess Sand
2824	to	2837	Mississippi
		2837	T. D.

Cut 12 1/4 in. hole to 129 ft. and run 131 ft. of 8 5/8 in. surface pipe, cemented with 90 sacks of cement at 129 ft. Plug down at 11:00 A. M., April 28, 1971. Cut 7 7/8 in. hole to 2837 ft. Hole dry and abandoned. Filled with mud to 125 ft. Set plug & put in 25 sacks of cement. Filled with mud to 40 ft. & set plug. Put in 10 sacks of cement, 2 sacks in rathole. Plugging completed at 7:00 P. M., May 2, 1971. Plugging completed by State Plugger, Gilbert Toman, Holyrood, Kansas.

TOPS: LANSING - 2182' BURGESS SAND - 2617' MISSISSIPPI - 2824'

Measurements taken from K. B.

CERTIFICATE

I, H. J. Flouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your MELANDER #3, located on the SE SW NW, Sec. 14-15-2W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Flouffe
 H. J. Flouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 3rd day of May, 1971.

Johnnie L. Schmidt
 Johnnie L. Schmidt - Notary Public



*no show, no tests, no Log,
 OK LRA*