

15-169-20010-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 9-10-67

LEASE NAME Melander

WELL NUMBER 2

4640 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 14 TWP. 15 RGE. 2 (XXX) (W)

COUNTY Saline

Date Well Completed 9-10-67

Plugging Commenced 3-7-94

Plugging Completed 3-9-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Lonny Bruce

ADDRESS 406 Ponderosa Ct., McPherson, Kansas 67460

PHONE# (316) 241-2938 OPERATORS LICENSE NO. 5611

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 5, 1994 (date)

by Ralph Tittel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 2820 Bottom T.D. 2856

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	soil, clay, sand	surface	125	8 5/8	125	none
Production	lime, shale	surface	2834	5 1/2	2834	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Drilled up plastic tubing to 2856 TD. Filled hole to 2700' with sand, capped with 5 sax cement to plug bottom. Spot cement plug at 300', let set up, circulated cement from 300' inside and outside 5 1/2 casing to plug top.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Scotts Well Service License No. 6819

Address P.O. Box 36, Roxbury, Kansas 67476

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lonny Bruce

STATE OF Kansas COUNTY OF McPherson, ss.

Lonny Bruce (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Lonny Bruce

(Address) 406 Ponderosa Ct., McPherson,

SUBSCRIBED AND SWORN TO before me this 16th day of March 19 1994

BEVERLY A. FOLCK
Notary Public - State of Kansas
My Appt. Expires 12-13-97

Beverly A. Folck
Notary Public

My Commission Expires: 12-13-97