


15-169-00447-00-00

WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit, Mail or Deliver Report to: Conservation Division, State Corporation Commission, 212 No. Market, Wichita, Kansas



Locate well correctly on above Section Plat

Saline County, Sec. 7 Twp. 15 Rge. 2 (E) (W) X
Location as 'NE/CNW/SW' or footage from lines. XXXXXX XXXXXX NW NE NE
Lease Owner Solar Oil Co.
Lease Name Clements Well No. #1
Office Address Box 903, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2-3-68 19
Plugging completed 2-6-68 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3228' Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Contains casing data for sizes 5 1/2", 13 3/8", and 8 5/8" with depths 3224', 80', and 279'.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3200'. Mixed and ran 5 sacks cement thru dump bailer.
Mudded hole to 275', set 15' rock bridge. Filled hole with 4 yards ready-mix from 260' to base of cellar.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7 day of February, 1968



October 1968

Sidney D. Miller Notary Public.

15-169-00447-00-00

DRILLERS LOG

Company: Solar Oil Company
Farm: Clements #1
Commenced: December 18, 1960

^{NW}
NE NE NE Section 7-15S-2W
Saline County, Kansas
Completed: December 28, 1960

Elevation:

0 - 60	sand
60 - 100	shale
100 - 885	lime & shale
885 - 1740	shale & lime
1740 - 2016	shale
2016 - 2320	shale & lime
2320 - 2675	lime & shale
2675 - 2875	Mississippian
2875 - 2930	lime
2930 - 2950	lime & shale
2950 - 3050	shale
3050 - 3221	lime
3221	Total Depth

RECEIVED
STATE CORPORATION COMMISSION
FEB 2 - 1968
CONSERVATION DIVISION
Wichita, Kansas

Set 80 feet of 13 3/8 inch surface pipe. Cemented with 95 sacks of common cement. Set 278 feet of 8 5/8 inch surface pipe cemented with 200 sacks of common cement with 2% gel and 2% calcium chloride.

Tops: Lansing -K.C. - 2016
Mississippi - 2675

Ran 3217 feet of 5 1/2 inch casing. Cemented with 75 sacks of cement.

A F F I D A V I T

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I, Allan Harms of the Harms-Burt Drilling Company being first duly sworn on oath state: I have knowledge of the facts, statements and matters herein contained and the same are true and correct.

Allan Harms

Subscribed and sworn to before me this 6 day of January, 1961

Mary E. Van Pelt
Notary Public

My commission expires January 20, 1962.