

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5616  
Name: CALVIN NOAH  
Address 1: 329 BIRCH ST  
Address 2: \_\_\_\_\_  
City: VALLEY CENTER State: KS Zip: 67147 + \_\_\_\_\_  
Contact Person: CALVIN NOAH  
Phone: (316) 755-1032  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
HUNTON Depth to Top: 2837 Bottom: 2840 T.D. 2840  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 115-20,746 - 00 - 00  
Spot Description: \_\_\_\_\_  
NW SE SW Sec. 6 Twp. 21 S. R. 3  East  West  
~~000~~ 1103 Feet from  North /  South Line of Section  
~~1,050-3674~~ Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: MARION  
Lease Name: HEYLAND Well #: 1  
Date Well Completed: 5/10/1981  
The plugging proposal was approved on: 12/4/2012 (Date)  
by: SHANE JONES (KCC District Agent's Name)  
Plugging Commenced: 1/12/2012  
Plugging Completed: 1/13/2012

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
HUNTON	OIL & WATER	SURFACE	8-5/8	200	0
		PRODUCTION	5-1/2	2837	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand open hole back to 2770' and dump 5 sacks cement on bottom with bailer. Fill hole with fresh water. Perforate 2 holes in 5-1/2" casing at 255'. Run tubing to 253' and circulate hole full of cement. Pull tubing and pump cement down 5-1/2" casing until cement circulated to top of 8-5/8 x 5-1/2 annulus. Used 165 sacks of cement total-Gressel Cementing.

RECEIVED  
JAN 24 2012

Plugging Contractor License #: 3038 Name: CYCLONE WELL SERVICE, INC.  
Address 1: P.O. BOX 522 Address 2: \_\_\_\_\_  
City: CANTON State: KANSAS Zip: 67428 + \_\_\_\_\_  
Phone: (620) 628-4428  
Name of Party Responsible for Plugging Fees: CALVIN NOAH  
State of KANSAS County, X SEDGWICK, ss.  
CALVIN NOAH  Employee of Operator or  Operator on above-described well,  
(Print Name)

KCC WICHITA

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: X Calvin Noah

