

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 33971  
Name: TriPower Resources, LLC  
Address 1: P.O. Box 849  
Address 2: \_\_\_\_\_  
City: Ardmore State: OK Zip: 73402 + \_\_\_\_\_  
Contact Person: W.B. Curry  
Phone: (580) 226-6700  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Mississippi Depth to Top: 2507 Bottom: 2591 T.D. 2633  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 015-23881-00-00  
Spot Description: \_\_\_\_\_  
E/2 NW NE Sec. 12 Twp. 23 S. R. 3  East  West  
660 Feet from  North /  South Line of Section  
1,650 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Butler  
Lease Name: Janzen Well #: 1  
Date Well Completed: 12/16/2010  
The plugging proposal was approved on: 1/26/2012 (Date)  
by: Patrick Shields (KCC District Agent's Name)  
Plugging Commenced: 1/27/2012  
Plugging Completed: 1/27/2012

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	220	0
		Production	5.5	2633	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Cast iron bridge plug set @ 2470'. Dump bailed 2 sx. Class A cement on top of CIBP. Perforated 5.5" at 270' with 4 shots. Filled casing with water and broke circulation. Consolidated Oil Well Services, LLC circulated from 270' to surface with 91 sx. 60/40 Poz mix cement + 4% gel. Shut down with annulus and casing standing full of cement. Cementing ticket #34060.

Plugging Contractor License #: 5870 Name: Phillips Well Service  
Address 1: P.O. Box 1263 Address 2: 315 N. Industrial Rd.  
City: El Dorado State: KS Zip: 67042 + 1263  
Phone: (316) 321-6650  
Name of Party Responsible for Plugging Fees: TriPower Resources, LLC

State of Oklahoma County, Carter, ss.  
W.B. Curry (Print Name)  Employee of Operator or  Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: W.B. Curry

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
FEB 02 2012  
KCC WICHITA