

**-Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
March 2009  
**Type or Print on this Form  
Form must be Signed  
All blanks must be Filled**

OPERATOR: License #: 33530  
 Name: Reif Oil & Gas Co, LLC  
 Address 1: PO Box 298  
 Address 2: \_\_\_\_\_  
 City: Hoisington State: KS Zip: 67544 + \_\_\_\_\_  
 Contact Person: Don Reif  
 Phone: ( 620 ) 786.5658  
 Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 009-25654-00-00  
 Spot Description: \_\_\_\_\_  
SE SW NW SE Sec. 10 Twp. 17 S. R. 14  East  West  
1,480 Feet from  North /  South Line of Section  
2,070 Feet from  East /  West Line of Section  
 Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
 County: Barton  
 Lease Name: Riedl Well #: 1  
 Date Well Completed: 1/30/2012  
 The plugging proposal was approved on: 1/30/12 (Date)  
 by: Ray Dinkel (KCC District Agent's Name)  
 Plugging Commenced: 1/30/12  
 Plugging Completed: 1/30/12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	971	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 170 sacks of 60/40 Poz, 4% gel, 1/4# flo-seal per sack, 1st plug @ 3450' with 25 sacks, 2nd plug @ 988' with 25 sacks, 3rd plug @ 400' with 80 sacks, 4th plug @ 40' to surface with wiper plug with 10 sacks, 30 sacks for rat hole, by Quality (Ticket #453), plug was down @ 7:45 pm on 1/30/2012.

**RECEIVED**  
**FEB 06 2012**  
**2-6-12**  
**KCC WICHITA**

Plugging Contractor License #: 33350 Name: Southwind Drilling  
 Address 1: 8 North Main Address 2: PO Box 276  
 City: Ellinwood State: Kansas Zip: 67526 + \_\_\_\_\_  
 Phone: ( 620 ) 564-3800  
 Name of Party Responsible for Plugging Fees: Reif Oil & Gas Co, LLC  
 State of Kansas County, Barton, ss.

Jill Wahlmeier  Employee of Operator or  Operator on above-described well,  
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jill Wahlmeier



Southwind Drilling, Inc.  
Plugging Orders & Reports

Lease: Riedl #1

Plugging Received from KCC Representative:

Name: Ray Dinkel Date: 1-30-12 Time: 11:00 AM

1st plug @ <u>20'</u> <sup>above arb</sup> feet, <u>25</u> sacks	Stands <u>55</u>
2nd plug @ <u>988</u> feet, <u>25</u> sacks	Stands <u>15</u>
3rd plug @ <u>400'</u> feet, <u>80</u> sacks	Stands <u>6</u>
4th plug @ <u>40'</u> <sup>wiper plug</sup> feet, <u>10</u> sacks	Stands <u>1</u>
5th plug @ _____ feet, _____ sacks	Stands _____

Mousehole: \_\_\_\_\_ sacks

Rathole: 30 sacks

Total Cement Used: 170 sacks

Type of cement: 60/40 pos 4% gel 1/4" Flo Seal per sack

Plug Down @ 7:45 p.m. 1-30-12 by quality cementing

Call KCC When Completed:

Name: Ray Dinkel Date: 1-31-12 Time: 9:40

RECEIVED  
FEB 06 2012  
KCC WICHITA