

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 08060
Name: Zenergy, Inc.
Address 1: 6100 S. Yale Ave /Suite 1700
Address 2: _____
City: Tulsa State: OK Zip: 74136 + _____
Contact Person: Keith Hill
Phone: (918) 488-6424
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Marrow Depth to Top: 5967 Bottom: 5970 T.D. 6490

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 119-20763 · 00 · 00
Spot Description: NE NE
S/2 SE Sec. 16 Twp. 35 S. R. 26 East West
4170 4180 Feet from North / South Line of Section
660 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Meade
Lease Name: Mathews Well #: 1-16
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 1/11/12
Plugging Completed: 1/16/12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Marrow	Oil, Gas, Water	Conductor	20	128	-0-
Chester	" " "	Surface	85/8	580	-0-
Basil Chester	" " "	Production	5 1/2	6484	1997

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @5900' W/2 sx cmt on top. Cut csg. @1997'. Ran tubing to 1820'. Pumped 50 sx. cmt 1800 to 1650. pumped 50 sx. cmt 900 to 750. pumped 50 sx. cmt 600 to 450'. and 15 sx. cmt 40' to surface. Cut off & weld steel ID plate 4' BGL. All portions of well bore filled W/9.5# 40 vis mud. Prior to plugging there was CIBP's set @6440' 9/8/87 and @6187' 9/14/87

Plugging Contractor License #: 8733 Name: Jerry Dunkin, Inc.
Address 1: P.O. Box 389 Address 2: _____
City: Enid State: Okla Zip: 73702 + _____
Phone: (580-237-6152)
Name of Party Responsible for Plugging Fees: Zenergy, Inc.
State of Oklahoma County, Tulsa ss.
Keith Hill Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
FEB 06 2012
KCC WICHITA

AR