


15-169-20015-00-00



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS
67460

December 5, 1967

COMPANY: GEORGE R. HESS & LARRY MOORE RANCH, INC.
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: *Donald* NELSON # 2
 LOCATION: C-E/2 NW/4, Sec. 14-15-2W,
 Saline County, Kansas
 COMMENCED: November 29, 1967
 COMPLETED: December 4, 1967
 ELEVATION:

0	to	38	Clay
38	to	125	Shale & Lime
125	to	730	Lime
730	to	1050	Lime & Shale
1050	to	1730	Shale & Lime
1730	to	2075	Lime & Shale
2075	to	2260	Shale & Lime
2260	to	2665	Lime
2665	to	2800	Lime & Shale
2800	to	2876	Shale & Lime
		2876	T. D.

Cut 12 1/4 in. hole to 126 ft. and run 128.50 ft. of 8 5/8 in. surface casing & cemented on bottom at 126 ft. with 85 sacks. Plug down at 3:00 P.M., November 29, 1967.
 Cut 7 7/8 in. hole to 2876 ft. and run 2846 ft. of 5 1/2 in. casing and cemented with 35 sacks cement 32 foot off bottom at 2844 ft. Plug down at 9:00 P.M., December 4, 1967.

TOPS: Brown Lime - 2110' Kansas City - 2175'

Measurements taken from K.B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Nelson #2, located on the C-E/2 NW/4 of Sec. 14-15-2W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Plouffe
 H. J. Plouffe, President



Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 5th day of December, 1967.

Ruth McVay
 Ruth McVay - Notary Public

My commission expires: December 18, 1969.....

MAR 05 1990

CONSERVATION DIVISION
Wichita, Kansas