


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Harper County. Sec. 11 Twp. 32S Rge. 7W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
NW SW NE

Lease Owner KRM Petroleum Corporation
Lease Name Harper Airport Well No. 1-11
Office Address Guaranty Bank Bldg., 817 17th St., Denver
Character of Well (Completed as Oil, Gas or Dry Hole) CO 80202
Dry Hole

Date Well completed January 16, 1981
Application for plugging filed Verbal Application 1981
Application for plugging approved Verbal Approval 1981
Plugging commenced January 16, 1981
Plugging completed January 16, 1981
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 1981

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,780'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	279'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,780 ft. (rotary total depth) to 290 ft. Set plug at 290 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 290 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole and 1 sack cement in water well.

STATE OF KANSAS
CONSERVATION DIVISION
Wichita, Kansas

JAN 30 1981

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg, Wichita, Kansas. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (~~employee~~ of owner ~~xxxxxx~~)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water - Suite 10, Wichita, KS
(Address) _____ 67202

SUBSCRIBED AND SWORN TO before me this 27th day of January, 1981

Elsie Willison
Elsie Willison - Notary Public.

My commission expires July 25, 1982



KANSAS DRILLERS LOG

COMPANY KRM Petroleum Corporation

sec. 11 T. 32S R. 7W
Loc. NW SW NE

FARM Harper Airport No. 1-11

COUNTY Harper

ROTARY TOTAL DEPTH 4,780'

COMM. January 5, 1981

COMP. January 16, 1981

CONTRACTOR H-30, INC. (Rig #3)

ISSUED January 27, 1981

CASING

10 3/4"

8 5/8" Set at 279' cemented w/200 sxs cement

ELEVATION 1,430' K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Red Bed	280'
Shale	1,122'
Shale and Lime	1,297'
Lime and Shale	4,780'
Rotary Total Depth	4,780'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting
STATE OF KANSAS

JAN 30 1981

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas)
) SS:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 27th day of January, 1981.

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

