


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Harper County. Sec. 16 Twp. 34S Rge. 7W ~~XK~~ (W)  
Location as "NE/CNW&SW&" or footage from lines C NE/4 SE/4 NE/4  
Lease Owner J. M. Huber Corp.  
Lease Name Cather Well No. 1  
Office Address Box 978, Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 1-21-56 19  
Application for plugging filed 1-22-56 19  
Application for plugging approved 1-22-56 19  
Plugging commenced 1-22-56 19  
Plugging completed 1-22-56 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5451 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	317'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Halliburton plug at 275' with 20 sacks cement spotted on top thru drill pipe. Filled with mud to 35'. Halliburton plug at 35' with 10 sacks cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor G-M-R Drilling Company  
Address P.O. Box 1033, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.  
W. W. Henson (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Henson  
Box 978, Liberal, Kansas  
(Address)



SUBSCRIBED AND SWORN TO before me this 31 day of January, 19 56  
7-27-57 Notary Public.

PLUGGING  
FILE SEC. 16 T. 34 R. 7W  
BOOK PAGE 34 LINE 2

NO. 1 CATHERWELL RECORD

LOCATION: NE SE NE, 16-34S-7W,  
Harper County, Kansas

Commenced: December 27, 1955

Operator: J. M. Huber Corporation  
302 Petroleum Building, Wichita, Kansas

Completed: January 22, 1956

Elevation:

Contractor: Graham-Messman-Rinehart Drilling Co.  
1005 East Second, Wichita, Kansas

Dry and Abandoned

Casing Record: 8 5/8" @ 317' w/250 sacks cement

....L O G....

Red Bed	44
Red Bed-Shale	1335
Shale	1763
Lime	1896
Lime-Shale	2058
Shale-Lime	2660
Lime-Shale	3849
Sand	3853
Sand-Shale	3950
Shale-Lime	4031
Lime-Shale	4150
Lime	4264
Sandy Shale-Lime	4298
Lime	4351
Shale Lime	4450
Lime-Shale	4531
Lime	4670
Lime-Miss Chat	4715
Lime	4789
Lime-Chert	4943
Chert-Lime	4957
Chert-Lime-Shale	4988
Shale-Lime-Chert	5033
Lime-Shale	5156
Viola Lime	5171
Lime	5194
Simpson Sand	5242
Sand	5265
Sand-Shale	5398
Arbuckle	5451 R.T.D.

The undersigned, GRAHAM-MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART DRILLING COMPANY

By: J. A. Gilliland

J. A. Gilliland

Subscribed and sworn to before me  
this 25th day of January, 1956

Jessie L. Lewis  
Notary Public

My Commission Expires: November 5, 1958

**PLUGGING**  
FILE SEC 16 T 34 R #1W  
BOOK PAGE 34 LINE 2