

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171-20,357-0000

LEASE NAME Gwen

WELL NUMBER 1

SPOT LOCATION SW SE NW

SEC. 2 TWP. 18S RGE. 31 (X) or (W)

COUNTY Scott

Date Well Completed 8/09/87

Plugging Commenced 11:45 A.M.
8/08/87

Plugging Completed 7:45 P.M.
8/08/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR BEREXCO INC.

ADDRESS 970 Fourth Financial Center

PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5363

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Dan Goodrow

Is ACO-1 filed? YES If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	346	8 5/8"	346	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

50 sk. @2300', 100 sk. @1600', 40 sk. @380', 10 sk. @40', 10 sk. RH; 10 sk. MH. Cement was
Cement was 60/40 Poz, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____
Address _____

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick, ss. SEP 29 1987

Evan Mayhew, Engineer of BEREXCO, INC. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: Wichita, Kansas
I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Evan Mayhew

(Address) 970 Fourth Financial Center

SUBSCRIBED AND SWORN TO before me this 14 day of Sept., 1987

Sherry Herrell
Notary Public
Sherry Herrell



NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 6 20 87
month day year

API Number 15- 171-20,357-0000

OPERATOR: License # 5363
Name BEREXCO INC.
Address 970 Fourth Financial Center
City/State/Zip Wichita, Kansas 67202
Contact Person Evan Mayhew
Phone (316) 265-3311

SW SE NW Sec. 2 Twp. 18 S, Rg. 31 X East West
2970 Ft. from South Line of Section
3630 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 990 feet
County Scott

CONTRACTOR: License # 5147
Name BEREDCO INC.
City/State Wichita, KS

Lease Name Gwen Well # 1
Ground surface elevation (2915) feet MSL

Well Drilled For: Well Class: Type Equipment:
 Oil SWD Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Depth to bottom of fresh water 100-150
Depth to bottom of usable water 1700

Surface pipe by Alternator 1-2 X
Surface pipe planned to be set 325'

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Conductor pipe required
Projected Total Depth 4600 feet
Formation Mississippian

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 6/16/87 Signature of Operator or Agent Evan C. Mayhew Title District Engineer

For KCC Use:
Conductor Pipe Required 200 feet; Minimum Surface Pipe Required 200 feet per Alt. 4 @
This Authorization Expires 12-17-87 Approved By 6-17-87

Set 325' of 8 5/8 on 8-1-87

SW SE NW Sec. 2 Twp. 18 S, Rg. 31 X East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ <u>Base Anhydrite</u>	feet depth with <u>50</u>	sxs of <u>50/50 Pozmix, 6% Gel</u>
2nd plug @ <u>Base Cheyenne-Dakota</u>	feet depth with <u>100</u>	sxs of <u>50/50 Pozmix, 6% Gel</u>
3rd plug @ <u>30' below base Surf.</u>	feet depth with <u>50</u>	sxs of <u>50/50 Pozmix, 6% Gel</u>
4th plug @ <u>40-0'</u>	feet depth with <u>10</u>	sxs of <u>50/50 Pozmix, 6% Gel</u>
5th plug @ <u>15</u>	feet depth with <u>15</u>	sxs of <u>10</u>
(2) Rathole with <u>15</u>		(b) Mousehole with <u>10</u>

PUSHER Howard Caine
TD 4590' FORMATION MISS.
SURFACE PIPE 8 5/8 @ 346'
ANHYDRITE 2276' ELEVATION 2915'
STARTING TIME & DATE 4:00 PM 8-8-87
COMPLETION TIME & DATE 7:45 PM
1st PLUG @ 2300 FT. W/ 50 SX
2nd PLUG @ 1600 FT. W/ 100 SX
3rd PLUG @ 380 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
~~WATER WELL PLUGGED W/ 15 SX~~
CEMENT COMPANY Halliburton
TECHNICIAN D.G.

60/40 pr. 670 gel

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1987
CONSERVATION DIVISION
Wichita, Kansas