

1 050887

171-19055-00-00 154

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-4377

C E/2 SW/4, SEC. 14, T 20 S, R 33 (W/E)

1320 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6234

Lease Name Pile Well # 3

Operator: The Maurice L. Brown Company

County Scott 152.23

Name & Address 200 Sutton Place Building

Well Total Depth 4684 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 13 3/8 feet 205

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Mid West Casing Pulling License Number 6497

Address P.O. Box F, Sublette, KS 67879

Company to plug at: Hour: 10 a.m. Day: 9 Month: 3 Year: 19 87

Plugging proposal received from Ed Eves

(company name) Mid West Casing Pulling (phone) 316-675-8349

were: 7" at 4624' PBD 1543' Perfs at 4264-97' Marm. 1645-55' Glor.

1st plug run tubing to 1500' and spot 50 sx cement, 2nd plug pump 50 sx cement on stub,

3rd plug pull to 700' and pump 50 sx cement, 4th plug pull to 240' and pump 60 sx cement,

5th plug pull to 40' and pump 20 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 10:30 a.m. Day: 17 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug ran tubing to 1540' and spotted 40 sx cement, shot casing at 1214', recovered 90' of 7", shot casing at 1350'

2nd plug ran tubing to 1350' and pumped 50 sx common cement,

3rd plug pulled tubing to 1200' and pumped 150 sx of common cement with 1 lb. of

celloflakes per sack mixed in, waited 4 hours and went in and tagged cement at 800',

4th plug hooked onto 13 3/8" surface casing and pumped 35 bbl. of bentonite mud

followed by 300 sx of Howcolite. Maximum pressure 200 psi and shut in 200 psi.

Remarks: Recovered 90' of 7" casing. Used common cement by Mid West Casing & Howcolite by (if additional description is necessary, use BACK of this form.) Halliburton.

Observe this plugging.

DATE 3-30-87

INV. NO. 16455

Signed Richard W. Lacey (TECHNICIAN) MAR 27 1987