

020231

5-29

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,384 -00-00
C SW SW, SEC. 31, T 20 S, R 33 W/EX
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5104

Lease Name Crist Well # 1
County Scott 156.00

Operator: Blue Goose Drilling Company, Inc.
Name & Address: P.O. Box 1413
Great Bend, KS 67530

Well Total Depth 4800 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Blue Goose Drilling Company, Inc. License Number 5104

Address P.O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 29 Month: 5 Year: 19 89

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling Company, Inc. (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2102-16'

1st plug at 2120' with 40 sx cement, 2nd plug at 1600' with 50 sx cement,
3rd plug at 600' with 40 sx cement, 4th plug at 208' with 40 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:45 p.m. Day: 29 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2120' with 40 sx cement,
2nd plug at 1600' with 50 sx cement,
3rd plug at 600' with 40 sx cement,
4th plug at 208' with 40 sx cement, 5th plug at 40-0' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 6-5-89

Signed Glenn Barlow (TECHNICIAN)

INV. NO. 24980
5-29

RECEIVED
STATE CORPORATION COMMISSION
JUN -2 1989
CONSERVATION DIVISION
Wichita, Kansas

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date April 18, 1989
month day year

C SW SW Sec 31: Twp 20' S, Rg 33 — East
 West

OPERATOR: License # 5104
Name: Blue Goose Drilling Company, Inc.
Address: P.O. Box 1413
City/State/Zip: Great Bend, KS 67530
Contact Person: Martin Miller
Phone: 316-792-5633

660 feet from South line of Section
4620 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: same
Name: Company Tools

County: Scott
Lease Name: Crist Well #: 1
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:

Oil ... Inj ... Infield Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWWO ... Disposal Wildcat ... Cable
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes no
Target Formation(s): Mississippi
Nearest lease or unit boundary: 660'
Ground Surface Elevation: unknown feet MSL

If OWWO: old well information as follows:

Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Domestic well within 330-feet: ... yes no
Municipal well within one mile: ... yes no
Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 1150'

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, total depth location: _____

Surface Pipe by Alternate: ... 1 2
Length of Surface Pipe Planned to be set: 200'
Length of Conductor pipe required: N/A
Projected Total Depth: 5000'

Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well farm pond ... other

DWR Permit #: _____
Will Cores Be Taken?: ... yes no
If yes, proposed zone: _____

208th Het 2 Reg.


AFFIDAVIT

PUSHER Martin Miller
TD 4800 FORMATION MISS
SURFACE PIPE 5 7/8 @ 208
ANHYDRITE 2102 ELEVATION _____
STARTING TIME & DATE 11:00 am 5-24-89
COMPLETION TIME & DATE 2:45 pm 5-24-89

1st PLUG @ 2120 FT. W/ 40 SX
2nd PLUG @ 1600 FT. W/ 50 SX
3rd PLUG @ 600 FT. W/ 40 SX
4th PLUG @ 201 FT. W/ 40 SX
RAT HOLE CIRCULATED W/ 40 - 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ _____ SX
CEMENT COMPANY Allied

TECHNICIAN: G.B.
RECEIVED
STATE CORPORATION COMMISSION
JUN - 2 1989
CONSERVATION DIVISION
Wichita, Kansas

8 5/8" - 200'
NO W.W.



WICHITA, KANSAS Date: 5-22-89 Agent: D.G.

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - File acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.