

To: 1 090300 7-9  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-171-20,440-00-60  
C SW NE, SEC. 18, T. 20 S, R. 33 W/E  
3300 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058  
Operator: American Warrior, Inc.  
Name & Address P.O. Box 399  
Garden City, KS 67846

Lease Name Mark Well # 1  
County Scott 157.95  
Well Total Depth 4860 feet  
Conductor Pipe: Size          feet  
Surface Casing: Size 8 5/8 feet 365

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereinafter indicated

Plugging Contractor American Warrior License Number 4058  
Address P.O. Box 399, Garden City, KS 67846

Company to plug at: Hour: 1:20 p.m. Day: 9 Month: 7 Year: 19 93

Plugging proposal received from Kevin Wiles  
(company name) American Warrior (phone) 316-275-9231

were: 4 1/2" at 4859' w/150 sx cement, PBTD 4817', Perfs at 4704-08, 4560-66'  
1st plug sand back to 4510' and dump 4 sx cement on top of sand through bailer,  
2nd plug at 2100' with 50 sx cement, 3rd plug at 1200' with 80 sx cement,  
4th plug at 400' with 50 sx cement,  
5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None   
Operations Completed: Hour: 3:40 p.m. Day: 9 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4500' and dumped 5 sx cement on top of sand through bailer, Plugged through casing:  
2nd plug pumped 80 sx cement at 1220',  
3rd plug pumped 50 sx cement at 400',  
4th plug pumped 10 sx cement at 40'.  
Circulated cement to pit.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1250' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I (did / ~~did not~~) observe this plugging.  
DATE 7-25-93  
INV. NO. 38198

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 13 1993  
CONSERVATION DIVISION  
WICHITA, KANSAS  
Signed [Signature]  
(TECHNICIAN)