

To: 1 030846
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SEP 2 1987
API NUMBER 15- 171-20,362-00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Operator: Falcon Exploration Inc.
Name &
Address 1531 Kansas State Bank & Trust Bldg.
Wichita, KS 67202

E/2 NW SW, SEC. 18, T 20 S, R 33 W/EX
1980 feet from S section line
4290 feet from E section line

Lease Name Harkness Well # 1
County Scott 156.49
Well Total Depth 4815 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 272

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302
Address 1720 Kansas State Bank Bldg., Wichita, KS 67202

Company to plug at: Hour: 10 p.m. Day: 1 Month: 9 Year: 19 87

Plugging proposal received from Jerb Ogle

(company name) Red Tiger Drilling Company (phone) 316-263-1201
were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2906' KB
Anhydrite 2100-70'

1st plug at 2160' with 50 sx cement, 2nd plug at 1320' with 80 sx cement,
3rd plug at 300' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:50 a.m. Day: 2 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement,
2nd plug at 1320' with 80 sx cement,
3rd plug at 300' with 40 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1987

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

I, Steve Durrant did (not) observe this plugging.

Signed Steve Durrant
(TECHNICIAN)

DATE 9-8-87

INV. NO. 18058
9-2 OCT 29 1987

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. August 14 1987 month day year

API Number 15- 171-20,362-0000

OPERATOR: License # 5316 Name Falcon Exploration Inc. Address 1531 KSB&T Bldg. City/State/Zip Wichita, Kansas 67202 Contact Person Kerry D. Parham Phone (316) 262-1378

E/2 NW/4 SW/4 Sec. 18 Twp. 20 S, Rg. 33 East West 1980 Ft. from South Line of Section 4290 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 990 feet County Scott

CONTRACTOR: License # 5302 Name Red Tiger Drilling Company City/State Wichita, Kansas 67202

Lease Name Harkness Well # 1 Ground surface elevation 2981 GL feet MSL

Well Drilled For: Well Class: Type Equipment: Oil Storage Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no Municipal well within one mile: yes no

If OWWO: old well info as follows: Operator N/A Well Name Comp Date Old Total Depth

Depth to bottom of fresh water 200' Depth to bottom of usable water 1400-1200 Surface pipe by Alternate 1-2

Surface pipe planned to be set 250' Conductor pipe required N/A Projected Total Depth 4800 feet

Formation Mississippian

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 8-10-87 Signature of Operator or Agent Kerry D. Parham Title Geologist

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 220 feet per Alt. This Authorization Expires 2-12-88 Approved By Paul 8-12-87

Handwritten notes: Move In 8-12-87 Paul Spud 8-20-87 D.G. 2501-87/8 flo WW

E/2 NW/4 SW/4 Sec. 18 Twp. 20 S, Rg. 33 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth, Formation, and Plug details. Includes rows for 1st through 5th plugs and rathole/mousehole details.



RECEIVED STATE CORPORATION COMMISSION

SEP 8 1987

CONSERVATION DIVISION Wichita, Kansas

Vertical log of well operations: PUSHED, TD 4815, SURFACE PIPE 878 @ 272, ANHYDRITE 2100 ELEVATION 2906, STARTING TIME & DATE 9-2-87, COMPLETION TIME & DATE 9-2-87, 1st PLUG @ 2160 FT. W/ 50X, 2nd PLUG @ 1320 FT. W/ 80SX, 3rd PLUG @ 300 FT. W/ 40, 4th PLUG @ 40-0 FT. W/ 10, RAT HOLE CIRCULATED W/ 15, MOUSE HOLE CIRCULATED W/ 15, WATER WELL PLUGGED W/ 40, CEMENT COMPANY 99-105X, TECHNICIAN Muller, Ken