

2 040295

API NUMBER 15- 077-21141 0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3/2 SW SE, SEC. 30, T. 34 S, R. 7 W E

330 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5840

Lease Name Walker Well # 1

Operator: Brandt Drilling Co Inc

County Harper 157.30

Name & Address 105 S. Broadway # 920

Well Total Depth 4840 feet

Wichita, Ks. 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 3/8 feet 370

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Brandt Drlg Co License Number 5840

Address Wichita Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Tim Brandt

(company name) Brandt Drlg Co. (phone) _____

were: _____

35 SX 900

35 SX 420

25 SX 60 on Solid Bridge

10 SX RH

10 SX MH

Plugging Proposal Received by DIST # 2 (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 0600 Day: 17 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT

The hole was filled with mud to surface. Drill pipe was run open ended to 900' where 35 sx of cement was spotted. The drill pipe was pulled to 420' and another 35 sx of cement was spotted. The drill pipe was pulled from the hole and a bridge was built at 60' and the hole was filled with 25 sx of cement. The Cat hole

Remarks: and Mouse hole were each circulated the 10 sx of cement. (If additional description is necessary, use BACK of this form.)

I (Agent) did not observe this plugging. Dated 10/27/86

Signed Steve Anderson (TECHNICIAN)

DATE 10-27-86

INV. NO. 15245

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date October 6, 1986
month day year

API Number 15- 077-21,141
S/2 SW 1/4 SE 1/4 Sec. 30 Twp. 34 S, Rg. 7 East
330 Ft. from South Line of Section
1980 Ft. from East Line of Section

OPERATOR: License # #5840
Name Brandt Drilling Co., Inc.
Address 105 S. Broadway, Suite 920
City/State/Zip Wichita, Kansas 67202
Contact Person Tim Brandt
Phone (316) 267-4335

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330 feet

CONTRACTOR: License # 5840
Name Brandt Drilling Co., Inc.
City/State Wichita, Kansas 67202

County Harper
Lease Name Walker Well # 1
Ground surface elevation feet MSL
Domestic well within 330 feet: ___yes no
Municipal well within one mile: ___yes no

Well Drilled For: Well Class: Type Equipment:
 Oil ___ SWD ___ Infield Mud Rotary
 Gas ___ Inj ___ Pool Ext. ___ Air Rotary
___ OWWO ___ Expl Wildcat ___ Cable

Depth to bottom of fresh water 75
Depth to bottom of usable water 350
Surface pipe by Alternate: 1 2 ___
Surface pipe planned to be set 350
Conductor pipe required
Projected Total Depth 4800 feet
Formation Mississippi

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 9-29-86 Signature of Operator or Agent Title President

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. 104
This Authorization Expires 4-1-87 Approved By 10-1-86 RCH/KCC

OCT 27 1986