

1 040873

7-29

API NUMBER 15- 007-20,834

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NE NW, SEC. 36, T 33 S, R 10 W/X  
4620 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Miller Well # 1

Operator: Pintail Petroleum, Ltd.

County Barber 148.39

Name & Address 225 N. Market, Ste. 300

Well Total Depth 4566 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 245

Abandoned Oil Well \_\_\_\_\_ X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D.S. & W. Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 11:15 a.m. Day: 29 Month: 7 Year: 19 94

Plugging proposal received from Art Stroube

(company name) D.S. & W. Well Servicing, Inc. (phone) 316-587-3361

Work: 4 1/2" at 4553' w/150 sx cement, Open hole 4553-66'

1st plug sand back to 4440' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 29 Month: 7 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4440' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3300' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-15-94 REV. NO. 40944

PCWD 08-15-94

Signed Stephen J. Pfeifer (TECHNICIAN)