



15-171-20057-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jim Lahar of B & B Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Incorporated,

Complete Address: Box #18407, Wichita, Kansas.

Lease Name: Miller Well No. J-1

Location: CNW-SE Sec. 16 Twp. 20 Rge. (E)(W) 33

County: Scott Total Depth 4800' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lahar was instructed to plug the well as follows:

679'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 675'.

Circulate hole with heavy mud. Pull DP to 960' and displace 140 Cu. Ft. cement thru DP. Pull DP, set plug @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

A. L. Pichele
Conservation Division Agent