

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-173-20051-0000

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 North Market
WICHITA, KANSAS

STATE RECEIVED
JUL 27 1970
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

July 23/70

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. JIM LAHAR of B & B Drlg. Co. has this

date requested permission to plug the following described well:
J.A. Allison & Publ. Petroleum

Mr. _____ guarantees payment of the plugging fee.

Operator's full Name: J.A. Allison & Publ. Petroleum

Complete Address: 1415 Wichita, Plaza Wichita, Kans.

Lease Name: Williams Well No. 1

Location: C SW NE Sec. 18 Twp. 25 Rge. 2W (E) (W)

County = Sedgwick Total Depth 593' Oil Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A X Lost Hole ✓

Mr. Lahar was instructed to plug the well as follows:

T.D. - 593'.

354' - 8 5/8" circulated. Lost circulation.

Mud high in hole. Push plug to 350'.

Mix 35 sacks, run thru drilling pipe.

Mud to 35' - 8 sacks cement to surface.

2 sacks cement in rat hole.

Very truly yours,

Ted E. Dewey
Conservation Division Agent