

State of Kansas



15-171-20004-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. F. W. Mallonee of Mallonee-Coppinger Oprns has this date requested permission to plug the following described well:

Mr. Mallonee guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Coppinger Operations, Inc.

Complete Address: 1207 Union National Bldg. Wichita, Kansas.

Lease Name: Beach Well No. 1

Location: Appr. CSW-SE Sec. 26 Twp. 20 Rge. (E)(W) 33

County Scott Total Depth 4935 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mallonee was instructed to plug the well as follows:

295'--8 5/8" Surface pipe, cement circulated with 275 Sx. Dakota section from 692' to 925'.

Circulate hole with heavy mud. Pull DP to 925' and displace 110 Sx. cement thru DP. Pull DP to 300' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

N. L. Nichols
Conservation Division Agent