



15-171-30006-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC - 6 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bob Sargent of Sargent's Casing Pulling has this date requested permission to plug the following described well:

Colo. Oil & Gas
Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Colorado Oil and Gas Corporation,

Complete Address: P.O. Box #158, Liberal, Kansas.

Lease Name: Dague Well No. 1-24

Location: CNW-SE Sec. 24 Twp. 20 Rge. (E)(W) 33

County Scott Total Depth 2716 Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

343' -- 7" Surface pipe, cement circulated.
2715' -- 4 1/2" Production casing cemented with 100 Sx. Top of cement @ 2125' (Temp. Survey). Top perforations from 2643' to 2680'.

Squeeze off bottom with 20 Sx. cement. Pull 4 1/2" casing to 660' and circulate heavy gel mud. Pull 4 1/2" to 600' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2" to 300' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2", set bridge @ 35' and fill to bottom of cellar with cement.

Very truly yours,

W. L. Nichols
Conservation Division Agent