

State of Kansas



15-171-20003-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 31 1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. F. W. Mallonee of Mallonee-Coppinger Oprns. has this date requested permission to plug the following described well:

Mr. Mallonee guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Coppinger Operations, Incorporated,

Complete Address: 1207 Union National Building, Wichita, Kans.

Lease Name: Petro Well No. 1

Location: Appr. CNE-NW Sec. 23 Twp. 20 Rge. (E)(W) 33

County Scott Total Depth 4720' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Mallonee was instructed to plug the well as follows:

296' -- 8 5/8" Surface pipe, cement circulated with 275 Sx. Dakota section from 565' to 670'.

Circulate hole with heavy mud, pull DP to 695' and set plug thru DP. with 85 Sx. cement. Pull DP to 315' and set plug thru DP with 20 Sx. cement. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent