



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission
CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 29 1959
 CONSERVATION DIVISION
 Wichita, Kansas

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date Sept 21, 1959, authorized the following plugging operation:

Operator's Full Name: Imperial Oil of Kans.
 Complete Address: Wallerney Kans.
 Lease Name: Hays Well No. 1
 Location: C-3-1-10 Sec. 17 Twp. 20 Rge. 33 (E) (W)
 County: Scott ^{NW NW} _{TD KCC} Total Depth: 4840
 Oil Well Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Run Pitts circulate hole with heavy mud, set
cementing plug at 550' and displace 20 sac cement
thru drill pipe, heavy mud to 310' set cementing
plug and displace 20 sac cement thru drill
pipe, heavy mud to 40' set and tie cementing
plug in place and dump 1/2 sac fulls and displace
10 sac cement, cementing to base of cellar

Very truly yours,

Signed: Gilbert P. Luker
 Conservation Division Agent