

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-001-21056-00-00  
<sup>SE</sup> SWSWNE Sec/Twp/Rge 16 - 26S - 21E  
2914 feet from south section line  
1976 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Daniels MUR65-0 (25)

Operator: State of Kansas

County Allen

Name & \_\_\_\_\_

Well Total Depth 675 feet

Address \_\_\_\_\_

Production Pipe: 2.5 Size Feet 675

AB oil well XXXX Gas Well \_\_\_\_\_

Surface Casing: 6.25 Size Feet \_\_\_\_\_

SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 4 Month: 11 2009

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by: Ryan M. Duling

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXX

Operations Completed: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 4 Month: 11 2009

Actual Plugging Report: Pulled 675' of 1" pipe. Ran 1" down inside 2.5" casing. The 2.5" casing is cemented in the 6.25" casing. Circulated cement through 1" pipe to surface. Pulled 325' of 1" pipe. Circulated cement through 1" pipe to surface. Pulled the rest of the 1" pipe. A total of 31 sacks of portland cement was used to plug this well. The well was cut off below grade and the location was restored.

Remarks: Contract #12391 Control #20100001-065 GPS 4-15-09 NAD 83 JAN 24 2011  
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Ryan M. Duling  
TECHNICIAN

KCC WICHITA

-95.11322136 37.78401 RECEIVED