

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-001-21057-00-00  
NE  
NWNWNE Sec/Twp/Rge 16 - 26S - 21E  
4697 feet from south section line  
1970 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Daniels MUR69-O (32)

Operator: State of Kansas

County Allen

Name & \_\_\_\_\_

Well Total Depth 700 feet

Address \_\_\_\_\_

Production Pipe: 2 Size Feet 700

AB oil well XXXX Gas Well \_\_\_\_\_

Surface Casing: \_\_\_\_\_ Size Feet \_\_\_\_\_

SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: \_\_\_\_\_ Day: 23 Month: 11 2009

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by: Ryan M. Duling

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXX

Operations Completed: Hour: \_\_\_\_\_ Day: 23 Month: 11 2009

Actual Plugging Report: Dug down beside the 2" casing with a backhoe approximately 4' and found the casing surrounded by cement. Pulled 700' of 1" pipe and pump with perforated nipple. Ran 1" pipe inside of 2" casing to 695'. Washed 1" pipe down inside of 2" casing to 698'. Circulated cement through 1" pipe inside 2" casing from 698' to surface. Pulled 350' of 1" pipe. Circulated cement through 1" pipe from 350' to surface. Pulled the rest of the 1" pipe out of the hole. Squeezed well with cement and shut in at 350 psi. A total of 27 sacks of portland cement was used to plug this well. The well was cut of below surface and the location was restored.

Remarks: Contract #12391 Control #20100001-069 GPS 4-16-09 NAD 83 JAN 24 2011  
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Ryan M. Duling  
TECHNICIAN

KCC WICHITA

RECEIVED  
-95.11321935 37.78890721