

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: State of Kansas

Name & _____

Address _____

AB oil well _____ Gas Well _____ SWD Well/ Input Well FOR XXXX D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLCLic. # 33749Address: 19245 Ford Road Chanute, KS 66720Company to plug at: Hour: _____ Day: _____ 1 Month: 3 2010Plugging proposal received from: Mike KepleyCompany Name: Kepley Well Service, LLC Phone: 620-431-9212Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by:

Ryan M. Duling

Plugging attended by Agent: All _____ Part _____

TECHNICIAN

None _____ XXXX _____

Operations Completed: Hour: _____ Day: _____ 1 Month: 3 2010Actual Plugging Report: Dug down beside the 6.25" surface casing with a backhoe approximately5'. Torched hole in the 6.25" surface casing to verify the 2.875" casing is cemented inside the 6.25" surfacecasing. Ran 1" pipe down the inside of the 2.875" casing to 745'. Circulated cement through the 1" pipeinside the 2.875" casing from 745' to surface. Pulled 375' of 1" pipe. Circulated cement through the 1"pipe inside the 2.875" casing from 375' to surface. Pulled the remaining of the 1" pipe. Topped the casingoff with cement. Squeezed casing to 550 psi. A total of 21 sacks of portland cement was used to plugthis well. The casing was cut off below surface and the site was restored.Remarks: Contract #12391 Control #20100001-076 GPS 4-16-09 NAD 83

(If additional description is necessary, use BACK of this form.)

-95.11398328 37.78348173
RECEIVED
JAN 24 2011
KCC WICHITA

I did not observe this plugging.

Signed:

Ryan M. Duling
TECHNICIAN