

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER  
~~SW SW NE~~  
~~SE SE NW~~

15-001-21188-00-01

Sec/Twp/Rge 16 - 26S - 21E

3118 feet from south section line

2639 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: State of Kansas

Name & \_\_\_\_\_

Address \_\_\_\_\_

AB oil well \_\_\_\_\_ Gas Well \_\_\_\_\_ SWD Well/ Input Well XXXX D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 2 Month: 3 2010

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by: \_\_\_\_\_

Ryan M. Duling

TECHNICIAN

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXX

Operations Completed: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 2 Month: 3 2010

Actual Plugging Report: Dug down beside the 6.25" surface casing with a backhoe approximately

4'. Torched hole in the 6.25" surface casing to verify the 2" casing was cemented inside the 6.25" surface

casing. Ran 1" pipe down the inside of the 2" casing to 710'. Circulated cement through the 1" pipe inside

the 2" casing from 710' to surface. Pulled 350' of 1" pipe. Circulated cement through the 1" pipe inside the

2" casing from 350' to surface. Pulled the remaining 1" pipe. Topped well off with cement. Squeezed well

to 750 psi. A total of 21 sacks of portland cement was used to plug this well. The well was cut off below

surface and the site was restored.

Remarks: Contract #12391 Control #20100001-082 GPS 4-16-09 NAD 83

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed: \_\_\_\_\_

[Signature]  
TECHNICIAN

KCC WICHITA

-95.11551649 87.7848839 RECEIVED  
JAN 24 2011