

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER

NE

SENE

15 - 001 - 03079-00-00

Sec/Twp/Rge 16 - 26S - 21E

4622 feet from south section line

138 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: State of Kansas

Name &

Address

AB oil well XXXX Gas Well SWD Well/ Input Well

Other well as hereinafter indicated:

Plugging Contractor: Kepley Well Service, LLC

Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: Day: 20 Month: 7 2010

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by:

Ryan M. Duling

TECHNICIAN

Plugging attended by Agent: All Part

None XXXX

Operations Completed: Hour: Day: 20 Month: 7 2010

Actual Plugging Report: Dug down beside the 8" surface casing. Torched hole in 8" casing to

verify 2" casing was cemented inside the 8" casing. Drilled cement from 15' to 30'. Broke through cement

and ran down 100'. Drilled cement from 100' to 150'. Ran 1" pipe down the inside of the 2" casing to 150'.

Circulated cement through the 1" pipe inside the 2" casing from 150' to surface. Pulled the 1" pipe.

Topped the 2" casing off with cement. The well was cut off below surface and the site was restored.

Remarks: Contract #12391 Control #20100001-003 37.78866 -095.10688 NAD83

(If additional description is necessary, use BACK of this form.)

GPS'd 4-14-09 By F.G.

I did not observe this plugging.

Signed:

TECHNICIAN

RECEIVED
JAN 24 2011

KCC WICHITA