

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-001-03092-00-00
SWSWNE Sec/Twp/Rge 16-26S-21E
3144 feet from south section line
2273 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Daniels MUR74-O

Operator: State of Kansas

County Allen

Name &

Well Total Depth 495 feet

Address

Production Pipe: 2 Size Feet 495

AB oil well XXXX Gas Well SWD Well/ Input Well

Surface Casing: 8 Size Feet

Other well as hereinafter indicated:

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: Day: 4 Month: 11 2009

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

 Plugging Proposal Received by: Ryan M. Duling

Plugging attended by Agent: All Part None XXXX

Operations Completed: Hour: Day: 4 Month: 11 2009

Actual Plugging Report: Ran 1" pipe down outside of 2" casing to 495'. Ran 1" down inside 2"

casing to 400'. Pumped 2 barrels of cement through 1" pipe on backside of 2" casing. Pumped 2 barrels

of cement through 1" pipe on inside of 2" casing. Circulated cement through 1" pipe on backside of 2"

casing to surface. Pulled 1" pipe on the backside of 2" casing out. Circulated cement through 1" pipe on

inside of 2" casing to surface. Pulled 1" pipe on inside of 2" casing out. Topped well off with cement. A

total of 162 sacks of portland cement was used to plug this well. The well was cut off below grade and the


location was restored.

Remarks: Contract #12391 Control #20100001-074 37.78465 -095.11425 NAD83 JAN 24 2011

(If additional description is necessary, use BACK of this form.)

CPSD 4-10-09 BY F.G.

I did not observe this plugging.

Signed: 
TECHNICIAN

RECEIVED

KCC WICHITA