

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-001-03095-00-00  
SESENW Sec/Twp/Rge 16 - 26S - 21E  
2914 feet from south section line  
2858 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Daniels MUR83-O

Operator: State of Kansas

County Allen

Name & \_\_\_\_\_

Well Total Depth 700 feet

Address \_\_\_\_\_

Production Pipe: 2.875 Size Feet 700

AB oil well XXXX Gas Well \_\_\_\_\_ SWD Well/ Input Well D & A

Surface Casing: 6.25 Size Feet \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 2 Month: 3 2010

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by: Ryan M. Duling

TECHNICIAN

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXX

Operations Completed: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 2 Month: 3 2010

Actual Plugging Report: Dug down beside the 6.25" surface casing with a backhoe approximately

5'. Torched hole in the 6.25" surface casing to verify the 2.875" casing was cemented inside the 6.25"

surface casing. Ran 1" pipe inside the 2.875" casing to 700'. Circulated cement through the 1" pipe

inside the 2.875" casing from 700' to surface. Pulled 350' of 1" pipe. Circulated cement through the 1" pipe

inside the 2.875" casing from 350' to surface. Pulled the remaining 1" pipe. Topped well off with cement.

Squeezed well to 550 psi. A total of 18 sacks of portland cement was used to plug this well. The casing

was cut off below surface and the site was restored.

Remarks: Contract #12391 Control #20100001-083 37.78403 -095-11027 NAD83 JAN 24 2011

(If additional description is necessary, use BACK of this form.)

GPSd 4-10-09 By F.G.

I did not observe this plugging.

Signed:

[Signature]  
TECHNICIAN

RECEIVED

KCC WICHITA