

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20491-00-01
Spot: SENE Sec/Twnshp/Rge: 17-35S-41W
3301 feet from S Section Line, 554 feet from E Section Line
Lease Name: HAYWARD D Well #: 3
County: MORTON Total Vertical Depth: 2650 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	572		WITH 450 SX CMT
PROD	5.5	2615	0	WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/24/2012 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. PLUG AT 1500' WITH 25 SX CMT. PLUG AT 600' WITH 70 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: NONE
Date/Time Plugging Completed: 01/24/2012 2:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMPED 200# HULLS & 25 SX CMT AT 2256'. 1ST PLUG AT 1500' WITH 25 SX CMT. 2ND PLUG AT 600' WITH 70 SX CMT. CMT TO SURFACE. PUMP 20 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS SPACE. PRESSURED TO 500 PSI.

Perfs:

Top	Bot	Thru	Comments
2339	2341		WINFIELD
2329	2331		WINFIELD
2286	2290		KRIDER
2275	2277		KRIDER
2268	2271		KRIDER
2256	2258		HERINGTON

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED
FEB - 2 2012
KCC DODGE CITY

RECEIVED
FEB 06 2012
KCC WICHITA

Form CP-73

2/10/12