

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-40095-00-01
Spot: NESESW Sec/Twnshp/Rge: 19-26S-5E
943 feet from S Section Line, 3015 feet from E Section Line
Lease Name: HOUSTON Well #: 28
County: BUTLER Total Vertical Depth: 2636 feet

Operator License No.: 34426
Op Name: AJ'S SERVICES, A GENERAL PARTNER
Address: 924 N. TOPEKA ST. PO BOX 1118
ELDORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	7	2567		
SURF	10	87		25 SX
PROD	7	2636		75 SX

Well Type: EOR UIC Docket No: E15896.2 Date/Time to Plug: 01/09/2012 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: JOHN BRICKLEY Company: AJ'S SERVICE Phone: (316) 322-7478

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/10/2012 11:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/77 JOINTS TBG @ 2440', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS CLASS A COMMON 3% GEL 1% CC AND DISPLACED IN CASING. CEMENT TICKET #34038. TAGGED CEMENT @ 2285', PERFORATED SQUEEZE HOLE @ 250'-251'. RIH W/TBG @ 255', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 80 SXS CLASS A COMMON 3% CC 1% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM, 1-9-2012. CONSOLIDATED CEMENT TICKET #34044. SDON. 1-10-2012, DUG OUT CELLER, CEMENT ON BACKSIDE OF 7" CASING, TOPPED WELL BACK TO SURFACE ON INSIDE OF 7" CASING FROM 40'. P & A COMPLETE.

Perfs:

Top	Bot	Thru	Comments
2610	2634	CSG	

Remarks: COMPLIANCE / 10 YR TA RULE

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

cc to MIC 2/08/12

RECEIVED
FEB 06 2012
2-6-12
KCC WICHITA

Form CP-2/3

2/10/12

✓