

LEASE NAME Oleen #1A

WELL NUMBER #1A

554 Ft. from S Section Line

4676 Ft. from E Section Line

SEC. 20 TWP. 16S RGE. 4 (E) or (W)

COUNTY Saline

Date Well Completed 8-13-94

Plugging Commenced 8-13-94

Plugging Completed 8-13-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Imperial Oil Properties, Inc.

ADDRESS 212 N. Market #513 Wichita, Kansas 67202-2013

PHONE# (316) 265-6977 OPERATORS LICENSE NO. 3869

Character of Well Dry

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-12-94 (date)

by Wichita (KCC District Agent's Name).

Is ACO-1 filled? in process If not, is well log attached? well log is attached

Producing Formation N/A Depth to Top _____ Bottom T.O. 3880

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		G.L.	679	8 5/8	Cemented	to surface

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Mix 35 sacks cement. Set plug at 3880. Fill to 730 with mud. Mix 40 sacks.
Set plug. Fill with mud to 60 ft. Mix 30 sacks. Fill to surface. Mix 15 sacks.
Pump down rat hole.

Name of Plugging Contractor Berentz Drilling Company, Inc. License No. 5892

Address P.O. Box 428 Eureka, KS 67045

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Imperial Oil Properties, Inc. 212 N. Market, #513
Wichita, KS 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Robert L. Williams, Jr., President of Imperial Oil Properties, Inc.
(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filled the the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 212 N. Market, #513, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 3rd day of September 1994

JAMES M. THOMAS Notary Public
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 8-26-97

My Commission Expires:
USE ONLY ONE SIDE OF EACH FORM

RECEIVED
SURRENDER TO COMMISSION
SEP 09 1994
09-07-1994
DIVISION
KANSAS
Form CP-1
Revised 05-88

15-1169-20312-00-00

LOG OF WELL

OLEEN #1A
100' SSW OF C SW SW
OF SEC 20-16S-4W
SALINE CO., KANSAS

OPERATOR : IMPERIAL OIL PROPERTIES, INC.
CONTRACTOR : BERENTZ DRILLING CO., INC.

COMMENCED : 7-28-94
COMPLETED : 8-13-94

CASING : 8 5/8 " - 679 ft CEMENTED W/420 SACKS

SOIL	6 ft
LIME	109 ft
SHALE	350 ft
SALT	399 ft
SHALE	630 ft
LIME	856 ft
LIME & SHALE	1070 ft
SHALE	1285 ft
SHALE & LIME	1538 ft
SHALE	1850 ft
SHALE W/LIME STEAKS	2052 ft
LIME & SHALE	2225 ft
SHALE	2298 ft
LIME	2400 ft
SHALE	2408 ft
LIME - LANSING	2815 ft
LIME - K.C.	3105 ft
SHALE	3145 ft
LIME - MISSISSIPPI	3438 ft
SHALE - KINDERHOOK	3650 ft
LIME - MAQUOKETA	3785 ft
SIMPSON	3865 ft
LIME - ARBUCKLE	3880 ft

RTD

RECEIVED
STATE CORPORATION COMMISSION
SEP 07 1994
CORPORATION DIVISION
WICHITA KANSAS