


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-169-19103-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 22 Twp. 16s Rge. 3W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE/4 NW/4 NW/4
Lease Owner Alfred Koehn
Lease Name Hansen Brothers Well No. I
Office Address Galva, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed May # II 19 60
Application for plugging filed May I # 19 61
Application for plugging approved May 3 19 61
Plugging commenced May 6 19 61
Plugging completed May II 19 61
Reason for abandonment of well or producing formation went dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3343' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2735'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with rock. Rock from 3343' to 3330'. Dumped 5 sx of cement. Muded hole to 210'. Made 10' of rock bridge. Dumped 20 sx of cement. Finished mudding hole to 35'. Made 5 ft. of rock bridge. Dumped 10 sx of cement, filling to the bottom of the celler.

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1961

CONSERVATION DIVISION
Wichita, Kansas

06-26-1961

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address P.O. Box 983 Hutchinson Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.
Alfred Koehn (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Alfred Koehn
Galva Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of Dec, 1961

My commission expires July 31 1962



W.D. Myers
Notary Public.

15-169-19103-00-00
W E L L R E C O R D

LEASE: Hansen Brothers WELL NO. 1

LOCATION: NE/4 NW/4 NW/4
 Section 22-16S-3W
 Saline County, Kansas

COMMENCED: May 3, 1960

COMPLETED: May 11, 1960
 (rotary)

OPERATOR: Alfred Koehn
 Galva, Kansas

CONTRACTOR: Melland Drilling Company, Inc.
 1111 North Main Street
 Hutchinson, Kansas

RECEIVED
 STATE GEOLOGICAL COMMISSION

MAY 3 1961
 05-03-1961
 CONSERVATION DIVISION
 Wichita, Kansas

CASING RECORD: 8-5/8" OD casing set at 316' and cemented with 200 sacks.
 5-1/2" OD casing set at 3339' and cemented with 50 sacks.

<u>FORMATION</u>	<u>LOG</u>
Surface soil & shale	25
Shale & Red Bed	100
Shale & shells	243
Anhydrite	316
Shale, lime & gypsum	430
Lime & shale	858
Shale & lime	1120
Shale & shells	1610
Shale & lime	1750
Lime & shale	1930
Lime	2020
Sand & shale	2200
Lime & shale	2780
Shale	2885
Lime	2906
Mississippi Lime	3085
Lime & shale	3160
Shale & lime	3240
Shale	3343
	ROTARY TOTAL DEPTH

LEASE: Hansen Brothers
n WELL NO. 1

LOCATION: NE/4 NW/4 NW/4
Section 22-16S-3W
Saline County, Kansas
COMMENCED: May 3, 1960
COMPLETED: May 11, 1960
(rotary)

OPERATOR: Alfred Koehn
Galva, Kansas

CONTRACTOR: Melland Drilling Company, Inc.
1111 North Main Street
Hutchinson, Kansas

CASING RECORD: 8-5/8" OD casing set at 316' and cemented with 200 sacks.
5-1/2" OD casing set at 3339' and cemented with 50 sacks.

<u>FORMATION</u>	<u>LOG</u>
Surface soil & shale	25
Shale & Red Bed	100
Shale & shells	243
Anhydrite	316
Shale, lime & gypsum	430
Lime & shale	858
Shale & lime	1120
Shale & shells	1610
Shale & lime	1750
Lime & shale	1930
Lime	2020
Sand & shale	2200
Lime & shale	2780
Shale	2885
Lime	2906
Mississippi Lime	3085
Lime & shale	3160
Shale & lime	3240
Shale	3343
	ROTARY TOTAL DEPTH

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1961

CONSERVATION DIVISION
Topeka, Kansas

06-26-1961