


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-169-00086-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Saline County. Sec. 22 Twp. 16S Rge. 3W (E) West (W)  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW SE SW  
Lease Owner National Associated Petroleum Company  
Lease Name E. Nelson Well No. 1  
Office Address 5th Floor Ritz Bldg. - Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 28 1951  
Application for plugging filed November 28 1951  
Application for plugging approved November 28 1951  
Plugging commenced November 28 1951  
Plugging completed November 28 1951  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation Depth to top Bottom Total Depth of Well 3577 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Kansas City	Water	2217	2869	10-3/4"	304.54'	None
Miss.	Water	2869	3099			
Kinderhook	Water	3099	3312			
Maquoketa	Water	3312	3386			
Viola	Water	3386	3462			
Simpson	Oil & Water	3462	3350			
Arbuckle	Water	3530	3577			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud.  
Set plug @ 160'.  
Built rock bridge and cemented w/20 sacks.  
Set bridge plug @ 20 feet.  
Cemented with 5 sacks.

RECORDED  
STATE CORPORATION COMMISSION  
JAN 19 1952  
CONS. DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Penguin Petroleum Company  
Address 709 Petroleum Building - Wichita, Kansas

STATE OF Oklahoma COUNTY OF Tulsa, ss.  
E. D. Ruse (employee of owner) or (owner & operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) E. D. Ruse, General Prod. Superintendent

5th Floor Ritz Bldg. - Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of January

My commission expires February 19, 1953

23-8390-s 6-51-20M



PLUGGING  
FILE SEC 271 16 R 3W  
BOOK PAGE 128 LINE 2

Company: National Associated Petro. Co.  
Farm: Nelson #1  
Comm: November 7, 1951  
Comp: November 22, 1951  
Contractor: Penguin Petroleum, Inc.

Sec. 22, W 10, N 24  
E 1/4 SW  
Saline County, Kansas  
Notary Public:  
Elevation: 1843'  
Notary Public No: 3577'

Casing: 10 3/4" @ 300 ccm w/ 250 sp.

0-20	Brown clay & sand
-25	Sand & pea gravel
-105	Sand & soft lime
-150	Blue & brown shale & lime chard
-160	lime
-215	Shale & shells
-300	Coment (hard)
-355	Shale & shells
-375	Sandy lime
-545	Shale & lime broken
-745	Shale & lime
-890	Broken lime
-1015	Sandy lime & shale
-1120	Shale & lime
-1290	Shale & red bed
-1340	Shale
-1430	Shale & shells
-1520	Shale & lime
-1580	Blue shale
-1610	White lime
-2070	Shale & lime
-2125	Douglas sand & shale
-2215	Shale & lime
-2260	lime
-2290	lime & shale
-2355	lime
-2400	lime & shale
-2440	Shale & lime
-2560	lime
-2722	lime & shale
-2735	Shale & lime
-2890	lime & shale
-2982	lime
-3022	Cherty lime & shale
-5170	lime
-3325	Shale
-3340	lime & shale
-3350	Viola lime
-3463	lime
-3486	Shale
-3500	Shale & lime & sand
-3505	Coring
-3515	Coring
-3520	Sandy shale
-3532	Shale & lime
-3577	Circulating

1951  
Nov 12 1951  
Nov 12-07-1951

R.U.T.D. 3577' R.T.D.

Certified to be a true copy of the well log as indicated on daily drilling reports.

22-16-51  
11-22-51

PENGUIN PETROLEUM, INC.

By Don McLeod

Subscribed and sworn to before me, the undersigned, a Notary Public in and for Sedgewick County, Kansas, this 12 day of November, 1951.

My Commission Expires:

October 15, 1952

B. D. Strickland  
Notary Public