


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-169-00261-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Saline County. Sec. 19 Twp. 16S Rge. 3W  West (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NW  
Lease Owner National Associated Petroleum Company  
Lease Name Bethany College Well No. 1  
Office Address 5th Floor Ritz Bldg. - Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 12-5-51 19. 51  
Application for plugging filed 12-5- 19. 51  
Application for plugging approved 12-5 19. 51  
Plugging commenced 12-5-51 19. 51  
Plugging completed 12-5 19. 51  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation Depth to top Bottom Total Depth of Well 3644 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lansing	Water	2389	2894	8-5/8"	436'	None
Miss.	Water	3045	3327			
Kinderhook	Dry	3327	3552			
Maquoketa dolo.	Water	3552	3618			
Viola xln.	Water	3618	3622			
Viola brk.	Water	3620	3622			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/heavy mud.  
Set a plug @ 160' w/15 sx cement.  
Filled w/heavy mud.  
Set a 15' cement plug in top of surface pipe, w/approx. 8 sx cement.

STATE CORPORATION COMMISSION

DEC 28 1951

CONS. DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Holm Drilling Company  
Address Box 7246 - Tulsa 18, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.  
C. Edwin Mohler (employee of owner) or (owner) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) C. Edwin Mohler, Chief Geologist

5th Floor Ritz Bldg. - Tulsa, Oklahoma (Address)

SUBSCRIBED AND SWORN to before me this 26th day of December 19. 51

My commission expires February 19, 1953

23-8390-s 6-51-20M



PLUGGING  
FILE SEC 19 16 R 30  
BOOK PAGE 130 LINE 24

15-169-00261-00-00

WELL LOG

Bethany College #1 Well

Location: NE/4 NE/4 NW/4 Sec. 19-168-3W  
Saline County, Kansas  
Commenced: November 19, 1951  
Spudded: November 20, 1951  
Completed: December 5, 1951

Operator: National Associated Petroleum Company  
Contractor: Holm Drilling Company

Casing Record: 8 5/8" - 425'

<u>Formation</u>	<u>Depth</u>
Shale	145
Sand and Shale	165
Shale and Shells	300
Anhydrite (Broken) Lost Circulation @ 300' and dry drilled to 425'	420
Anhydrite	425
Shale	475
Shale and Lime	1085
Shale and Shells	1880
Shale and Lime	2045
Lime	2250
Shale and Shells	2415
Lime and Shale	2440
Lime	3083
Cherty lime	3254
Shale, Lime and Cherty	3281
Shale and Lime	3370
Shale	3553
Cored 3553 to 3557	
Shale and Lime	3624
Lime	3641 T.D.

Note - All above depths are rotary bushing measure. Deduct 5' for ground level measure.

Holm Drilling Company

by J. C. Hatfield  
J. C. Hatfield - Secy-Treas.

**PLUGGING**  
FILE SEC 19 T 16 R 34  
BOOK PAGE 13 LINE 2

12-28-1951